



DarranDIWHY

Darran Drape
VAT # 07506831072
Lochee, Dundee, UK
07506831072
darran.drape@gmail.com

ESTIMATE
EST0164

DATE
15/06/2025

TOTAL
GBP £18,740.00

TO

St Salvador’s Church Hall

Carnegie St
Dundee

DESCRIPTION	RATE	QTY	AMOUNT
Gents toilet	£7,370.00	1	£7,370.00
Remove and dispose of all existing fixtures and saniware. Rewire for new layout. Build new cubicle floor to ceiling (new height) Wetwall all existing and new built walls. Lower ceiling to 2.4m, PVC panelling with down lights. Lay new LVT flooring Install new Toilet in cubicle, 2x new urinals, 2x new sinks (anti scald valves) Fit new hand dryer in new location, new extractor fan. Prepare and paint inside of main door			
Ladies toilet	£7,480.00	1	£7,480.00
Remove and dispose of all existing internal fixtures and saniware. Rewire for new layout. Build 2x new cubicles floor to ceiling (new height. Wetwall all existing and new built walls. Lower ceiling (2.4m) PVC panelling with down lights. Lay new LVT flooring Install new toilets in cubicles and 2 x new sinks (anti scald valves. Fit new hand dryer in new location and extractor fan. Prepare and paint inside of entrance door and emergency exit doors.			

DESCRIPTION	RATE	QTY	AMOUNT
Disabled toilet	£3,890.00	1	£3,890.00
Remove and dispose of all internal saniware. Retain baby changing table for re instalation.			
Wetwall all internal walls			
Lower ceiling to 2.4m, PVC panelling with down lights.			
Lay new LVT flooring.			
Install full disable saniware kit with handle / rails and anti scald sink valve.			
Fit new extractor fan.			
Refit baby changing table.			
Prepare and paint interior of door.			
TOTAL			GBP £18,740.00

All prices provided are assumong there are no structural issues preventing works progressing